

EXTENT OF WORK
NORTH STREET DRAIN
Municipality of Bayham

Our Job No. 224032

November 21, 2024

MAIN DRAIN

Sta: 0+000 - 0+126

Installation of the following HDPE pipe including supply & installation of bedding and backfill materials, including the removal of existing.

126 meters of 600mm dia. H.D.P.E. pipe \$ _____ L.S.
Supply of the above listed pipe \$ _____ L.S.

Supply and install one 900mm x 1200mm catchbasin and core into existing 1200mm x 1500mm ditch inlet catchbasin, including grates, berms, ditching, removal and disposal of existing catchbasins as required. \$ _____ L.S.

Restoration of gravel laneway \$ _____ L.S.

Hydroseeding of excavated area (Approx. 650m²) \$ _____ L.S.

Support hydripoles as required \$ _____ L.S.

Exposing and locating existing tile drains and utilities \$ _____ L.S.

BRANCH 'A'

Sta: 0+047 - 0+581

Installation of the following HDPE pipe including supply & installation of bedding and backfill materials

202 meters of 250mm dia. H.D.P.E. pipe \$ _____ L.S.
128 meters of 300mm dia. H.D.P.E. pipe \$ _____ L.S.
295 meters of 375mm dia. H.D.P.E. pipe \$ _____ L.S.
Supply of the above listed pipe \$ _____ L.S.

Supply & install one 600mm x 1200mm ditch inlet catchbasin and eight 600mm x 600mm catchbasins, including grates, berms, leads, and ditching \$ _____ L.S.

Clearing trees/brush \$ _____ L.S.

Seeding of excavated area (Approx. 600m²) \$ _____ L.S.

Exposing and locating existing tile drains and utilities \$ _____ L.S.

NOTE: The Extent of Work is to be attached to the Tender Form.

COMPANY NAME: _____

ADDRESS: _____

TELEPHONE NO: _____ DATE: _____

NOTE: This "Extent of Work" form has been prepared for the convenience of the Contractor and he is to use this summary in conjunction with the plan and profile, tender form and standard specifications available from the Clerk to tender this project. In case of any inconsistency or conflict between the drawings and this "Extent of Work", the drawings shall take precedence over the "Extent of Work".